

**Tyler County Airport
Bid Specifications on Options # 1, 2 & 3
ID 06142021AIRPORT
Airport**

RE: Bid- Build Roads for Hangers & Access to Runway

Option #1 – Main hanger road with 2 access roads to Runway – Approx 22,300 s.f.

- A. Prep Area
Strip off grass & topsoil & haul off to onsite area. Blade up roads, water & roll for compaction. Grade for level & water runoff.
- B. Haul in & place green road base for sub-base. Place & roll for 4" compacted base-
approx. 600 tons of road base- in place compaction 600 tons
- C. Haul & lay asphalt – approx. 22,300 s.f. 2" compacted – 295 tons

Option # 2 – Access road from hanger area to main airport area- approx. 450' x 20' = 9000 s.f.

- A. Prep road area
Strip off grass & topsoil & haul off to onsite area. Blade up road, water & roll for compaction. Grade for level & water run off
- B. Haul in & place green road base for sub-base. Place & roll for 4" compacted base-
approx. 450' x 20' = 9000 s.f.
- C. Haul in & lay asphalt 2" compacted – approx 450' x 20'

Option # 3 – Road to Hanger # 7

- A. Prep Area
Cut off end of old asphalt & build 170' x 20' road – approx 3400 s.f.
Strip off grass & topsoil. Blade up road, level, water & roll sub-base
- B. Haul & place 25 tons road base in place & roll for compaction
- C. Lay 42 tons asphalt 2" compacted