

Pre-Bid Addendum to the Construction Documents

Date: **06/17/20**
Addendum #: **2**
Project Name: **Waco St. Support Services Building, Hillsboro, TX**

General;

The shutoff valve for the fire line will be located above ground, in the maintenance closet off of the sally port.

Drawings;

The mechanical drawings refer to new fire alarm system components that would be part of Alternate #1. The fire alarm system work will not be included in base or Alternate bids at this time. If a fire alarm system is added to the building, it will be by owner at a later date. Changes to the plans include;

1. Sheet E2.01 - Delete the fire alarm system note.
2. Sheet E5.01 – Delete Fire Alarm System Specifications.

Attachments;

n/a

END OF ADDEDDUM #2