

Pre-Bid Addendum to the Construction Documents

Date: **06/08/20**

Addendum #: **1**

Project Name: **Waco St. Support Services Building, Hillsboro, TX**

Questions;

1. What is the status of the existing roof insulation?

The existing roof was built with 2-1/4" of rigid insulation over the metal decking.

Drawings;

The drawings have been updated to show scope of work changes to the demolition and construction of above project. The changes include;

1. Delete the demolition of 2'x6' door in Area 1. The door will be closed and locked.
2. Remove all FFE in Janitors closet, cap or plug all exist utilities.
3. Remove two sliding doors into the isolation cell.
4. Remove the smoke barrier above the ceiling areas.
5. Remove the two stucco ceilings above two halls between Area 1 and Area 2.
6. There will be no spray foam insulation in the rooms with existing gypsum ceilings. This is reflected on the plans.
7. Clarification note to grind smooth any protrusions from the slab and plug resulting holes with concrete.
8. Four (4) copper pipes at the northwest corner of Area 1 were abandoned in the process of the previous demolition process. These pipes are to be capped in place.

Attachments;

Drawing D1.01
Drawing A1.01

END OF ADDEDDUM #1



[Handwritten signature]
06/08/20